

ADDENDUM NO. 1

SECURE AREA ELECTRIC AND WALL UPGRADES

PROPONENTS MUST ACKNOWLEDGE, BY SIGNATURE, RECEIPT OF THIS ADDENDUM NO. 1 ON THE PROPOSAL FORM.

1. Replace Scope of Work Item #1a with: “Remove section of existing wall and discard.”
2. Add to Scope of Work Item #1b: Provide and install a nominal 4” stud wall covered with 5/8 drywall. Wall to be on drawing APD 101, approximate size is 25 ft. long and 103 inches tall. Height shall match existing wall. Carpet shall be removed from under wall, scraps to be turned over to airport. Drywall shall be taped and fastener heads filled. Top of wall and side wall where it meets private screening booth to be covered in drywall and finished. Provide and install primer and latex paint, contractor to provide Airport with color section. Final wall shall be of professional quality suitable for the location and use.
3. Replace Scope of Work Item #1c with: Move electric and communication connection to new locations shown on drawing EPD 101. Provide and install any necessary material to extend lines to new locations.
4. Add to Scope of Work Item #1d: Carpet to be removed from under walls at new location, scraps to be turned over to airport. Booth can be down for one day. Power and communication for the booth shall be completed by end of project.
5. Add to Scope of Work Item #1f: Provide and install vinyl resilient base on bottom of both sides of wall. Provide color samples for Airport.
6. Delete from Project Requirements item #4. (badging will not be required; Airport will provide an escort when contractor is in the secure area).
7. Delete from Form of Response Items #1 and #2. (Please be sure to submit the Proposal Form and the America CARES Act Certification for a complete bid submission)