GENERAL NOTES:

- 1. THE CONTRACTOR SHALL VERIFY ALL DEPTHS AND LOCATIONS OF EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION. ANY DISCREPANCIES WITH THE CONSTRUCTION PLANS FOUND IN THE FIELD SHALL BE BROUGHT IMMEDIATELY TO THE ATTENTION OF GEI'S ENGINEER WHO SHALL BE RESPONSIBLE FOR REVISING THE PLANS AS APPROPRIATE. ALL REVISIONS SHALL BE BROUGHT TO THE ATTENTION OF THE CITY ENGINEER. PLAN REVISIONS MAY NEED ZONING ADMINISTRATOR AND CITY ENGINEER APPROVAL.
- 2. ALL AREAS DISTURBED OR EXPOSED DURING CONSTRUCTION SHALL BE REVEGETATED IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. HOWEVER, THE TYPE OF REVEGETATION MUST EQUAL OR EXCEED THE TYPE OF VEGETATION PRESENT BEFORE CONSTRUCTION UNLESS OTHERWISE SPECIFIED.
- 3. PRIOR TO ANY CONSTRUCTION, A PRECONSTRUCTION CONFERENCE BETWEEN THE DEVELOPER, THE CONTRACTOR, UTILITY COMPANIES, ANY AFFECTED PARTIES, AND ANY OTHER ENTITY THE CITY OR DEVELOPER MAY REQUIRE SHALL CONVENE.
- 4. THE CONTRACTOR OR HIS/HER DESIGNATED AGENT SHALL KEEP ACCURATE RECORDS OF ALL CONSTRUCTION THAT DEVIATES FROM THE PLANS. THE CONTRACTOR OR HIS/HER DESIGNATED AGENT SHALL FURNISH THE CITY OF MARQUETTE ACCURATE "AS-BUILT" DRAWINGS FOLLOWING COMPLETION OF ALL CONSTRUCTION. THESE "AS-BUILT" DRAWINGS SHALL MEET WITH THE SATISFACTION OF THE CITY ENGINEERING DEPARTMENT PRIOR TO FINAL ACCEPTANCE. FINAL "AS-BUILTS" DRAWINGS SHALL BE DELIVERED TO THE ENGINEERING DEPARTMENT.
- 5. PRIOR TO ANY CONSTRUCTION, THE CONTRACTOR OR HIS/HER DESIGNATED AGENT SHALL APPLY FOR AND SECURE ALL PROPER PERMITS FROM THE APPROPRIATE AUTHORITIES, SUCH AS, BUT NOT LIMITED TO, THE CITY OF MARQUETTE, MICHIGAN DEPARTMENT OF ENVIRONMENTAL GREAT LAKES AND ENERGY, COUNTY OF MARQUETTE, ETC.

PROJECT SAFETY NOTES:

 PROJECT SAFETY SHALL BE IN ACCORDANCE WITH THE LAWS OF THE STATE OF MICHIGAN AND THE MICHIGAN OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION'S CURRENT REGULATIONS.

TRAFFIC CONTROL NOTES:

- ANY METHODS, STREET MARKINGS AND SIGNAGE NECESSARY FOR WARNING MOTORISTS, WARNING PEDESTRIANS OR DIVERTING TRAFFIC DURING CONSTRUCTION SHALL CONFORM TO THE MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, LATEST EDITION.
- 2. ALL PUBLIC STREETS THAT ARE TO BE CLOSED OR INTERRUPTED DUE TO THE CONSTRUCTION ACTIVITIES WILL REQUIRE COORDINATION WITH THE CITY OF MARQUETTE ENGINEERING DEPARTMENT FOR A PUBLIC SERVICE ANNOUNCEMENT. A MINIMUM OF 72 HOURS NOTICE WILL BE GIVEN TO THE CITY ENGINEERING DEPARTMENT FOR SAID CLOSURES OR INTERRUPTIONS.
- 3. PARKING RESTRICTIONS MUST BE POSTED 24 HOURS BEFORE WORK STARTS AND WILL BE AT THE EXPENSE OF THE CONTRACTOR/DEVELOPER. CONTACT THE POLICE DEPARTMENT AND PUBLIC WORKS DEPARTMENT WHEN RESTRICTIONS ARE PLACED.
- 4. THE HOURS OF CONSTRUCTION OPERATIONS WILL FOLLOW THE NOISE RESTRICTIONS AS PER THE CITY OF MARQUETTE NUISANCE ORDINANCE AND AS SPECIFIED IN THE CITY OF MARQUETTE STANDARD CONSTRUCTION SPECIFICATIONS.

CONSTRUCTION NOTES (APPLICABLE TO ALL SHEETS):

- 1. AT NO TIME SHALL EXCAVATED MATERIAL(S) OR IMPORTED MATERIAL(S) BE STOCKPILED ON PAVED SURFACES. IF THE PAVED SURFACE IS DAMAGED BY THE CONTRACTOR AS A RESULT OF STOCKPILING EXCAVATED MATERIAL(S) OR IMPORTED MATERIAL(S) ON PAVED SURFACES, THE CONTRACTOR SHALL BE REQUIRED TO REPAIR THE PAVED SURFACE AT NO ADDITIONAL COST TO THE OWNER.
- 2. AT NO TIME SHALL TRACK EQUIPMENT BE PERMITTED TO TRAVEL ON OR ACROSS PAVED SURFACES WITHOUT PROVIDING ADEQUATE PROTECTION BETWEEN THE TRACKS AND PAVED SURFACE. IF THE PAVED SURFACE IS DAMAGED BY FAILURE TO PROVIDE ADEQUATE PROTECTION BETWEEN THE TRACKS AND PAVED SURFACE, THE CONTRACTOR SHALL BE REQUIRED TO REPAIR THE PAVED SURFACE AT NO ADDITIONAL COST TO THE OWNER.
- 3. SAFETY REQUIREMENTS SHALL BE CONFORMED TO AND ALL OPERATIONS SHALL BE CONDUCTED SO AS NOT TO DAMAGE, DESTROY, OR ENDANGER THE INTEGRITY OF THE ROADWAY PAVEMENT STRUCTURE. ALL WORK WITHIN THE PUBLIC RIGHT-OF-WAY SHALL BE CONDUCTED IN ACCORDANCE WITH MIOSHA SAFETY RULES AND REGULATIONS.

CTE ROOFING REPLACEMENT MARQUETTE SENIOR HIGH SCHOOL MARQUETTE, MICHIGAN

MARQUETTE AREA PUBLIC SCHOOL MARQUETTE, MICHIGAN



MARQUETTE SENIOR HIGH SCHOOL - CTE WING ROOFING REPLACEMENT

Project 2403180 | April 2024

24 Fig. 1

